



STANDARD KERB AND CHANNEL




VEHICLE CROSSING

TYPE 2

EXTRUDED KERB AND CHANNEL



PRAM CROSSING




STANDARD KERB

VEHICLE CROSSING

TYPE 3

BASALT OR PRE-CAST KERB ONLY




STANDARD KERB


VEHICLE CROSSING

TYPE 4

EXTRUDED KERB ONLY



TYPE 5
BASALT OR PRE-CAST KERB EDGING
(75x150)



TYPE 6
CONCRETE DISH CHANNEL

NOTES KERB & DISH CHANNEL ONLY (EXTRUDED)

- 1. Jointing**
Precast kerb 10mm. min. neatly pointed with cement mortar. Extruded kerbs cracking control joints formed or saw cut to a minimum depth of 30mm at max. 4.00m. intervals to coincide with concrete footpath joints (where the kerb is adjacent to the footpath). Crack control joints between bluestone kerb blocks shall be approximately 20mm wide (measured at the top and front faces) with neat square jointing 2 to 4 mm proud. Joints to be located either side of vehicle crossings.
- 2. Bedding**
Kerbings to be laid on 300mm. min. GAP65 subbase in roads and 100mm GAP40 in footpaths (Where subgrade CBR>5). If the subgrade CBR<5 then roads and footpaths are to be undercut and backfilled with appropriate backfill material
- 3. Concrete Grades**
Precast kerb blocks 20 MPa. In-Situ channel and haunching 20 MPa. Extruded concrete 25 MPa.

PREPARED BY OPUS:



AUCKLAND CITY
Transport

KERBS AND CHANNELS

SCALE : NTS.

DRAWN : PH

ISSUE DATE : 11/2008

APPROVED :

PLAN No. ISSUE B

2008/0203